

Table of Contents

Page 4Construction Funding
 Page 5.....Construction Expenditure Distribution
 Page 6.....District 1 Construction Program
 Page 12.....District 2 Construction Program
 Page 16.....District 3 Construction Program
 Page 22.....District 4 Construction Program
 Page 28.....District 5 Construction Program
 Page 32.....District 6 Construction Program
 Page 36.....District 7 Construction Program
 Page 40.....District 8 Construction Program
 Page 44Projects Under Development
 Page 45Projects Advanced to the FY-2011
 Program from the 5-Year or
 Under Development Programs

Note: Project cost estimates contained in this publication represent the planning estimates of the total costs of a project. These include: preliminary engineering, right-of-way, utilities, construction, and construction engineering. These estimates are derived from analyses of current prices and are adjusted for inflation.

transportation.nebraska.gov

Abbreviations and Definitions

Road building, like every other occupation, has its own vocabulary, its “shorthand” and its abbreviations. The following are those most commonly used in this booklet:

Armor Coat - A thin covering of gravel placed after the roadway surface has been sprayed with asphalt.

Br. (Bridge) - Structure over stream or roadway. May include new construction, reconstruction, widening or rehabilitation of existing structure. May include reconstruction of approaches.

Conc. (Concrete)

Crack Seal - The sealing of random and reflective cracks in concrete and bituminous pavements with a hot-pour type sealer.

Culv. (Culverts) - Pipes or concrete boxes necessary to carry water under the roadway.

Gr. (Grading) - The movement of earth needed to construct the project as designed.

Grinding - Diamond grinding to smooth the surface of a concrete pavement.

Interchange - Construction of a new interchange or revision of existing interchange and connecting roads.

Joint Seal - The replacement of the seal at the transverse and longitudinal joints in concrete pavements with a hot-pour type sealer.

Microsurfacing - A thin layer of asphalt slurry material spread to remove rutting and surface irregularities in asphalt pavements.

Mill, Inlay - The milling of a certain thickness of asphalt surfacing from the driving lanes and replacement with a like thickness of new asphalt surfacing.

Pvmt. (Pavement)

Resurf. (Resurfacing) - Additional layer of surfacing material placed on top of existing hard-surfaced road to improve rideability and strength of roadway. May include minor widening of roadway and structures.

S. Shld. (Surfaced Shoulders) - Hard surfacing the shoulders of an existing or new hard-surfaced road. May include minor grading and structure widening.

Str. (Structures) - Culverts, bridges and/or viaducts, either new or reconstructed.

Surf. (Surfacing) - Hard surfacing, either concrete or bituminous.

Underpass - Structure on roadway passing under railroad tracks.

Urban - Construction of divided or undivided curbed roadway in an urban area. May include grading, structure and incidental work.

Viaduct - Structure over a railroad or other roadway.